

FROM RESEARCH TO INDUSTRY

cea




www.cea.fr

HIGH INTENSITY LIGHT ION SOURCES

O.Tuske
Irfu / SACM



Sources for research



Research for sources

CSI, January 14-15, 2015

Principle of an ECR ion source

- SILHI source for IPHI project


Results in recent years

- IFMIF : in Japan
- SPIRAL2 : in Caen
- FAIR : Installation of a new ion source in 2015

R&D

- Simulations with WARP code
- ALISES ion source


ECR PRINCIPLE




$$W_{cydo} = \frac{eB}{m} \begin{matrix} \ddot{u} \\ \ddot{v} \\ \ddot{y} \\ \ddot{p} \end{matrix} \quad W_{cydo} = W_{HF}$$

for B = 875 Gauss


Axcel code




Magnetic and electrostatic calculations





Opera code



H⁺/D⁺
100mA @ 100kV
Pulsed or CW



H⁺ ou D⁺ beam






First beam in 1996, still in operation

2015 GOAL :
H⁺ beam injection into the IPHI RFQ

ION SOURCES DEVELOPPED AT CEA SACLAY

Projct /Source	High Voltage	Extracted intensities	Operation mode	Magnetic Configuration
SILHI → IPHI	100kV	100mA H ⁺	CW / Pulsed	Coils
SPIRAL2	20kV 40kV	5mA H ⁺ 5mA D ⁺	CW / Pulsed	Permanent Magnets
SILAP-1	40kV	40mA H ⁺	Pulsed 50% DC	Permanent Magnets
IFMIF EVEDA	100kV	140mA D ⁺	CW / Pulsed	Coils
ALISES	30kV 100kV	18mA H ⁺ Not yet tested	Pusled 20% DC	Coils
SILHI2	50kV	40mA H ⁺	CW / Pulsed	Permanent Magnets
FAIR	95kV	Not yet tested	Pulsed 4% DC	Coils



RECENT RESULTS

IFMIF

SPIRAL2



FAIR

The Acceptance tests have been performed in November 2012:

- Beam characterization was made with D+ beam in both pulsed and continuous modes.
- Species fraction has been measured after 1st solenoid
- Emittance scanner was measured at end of the LEBT (after cone)

D⁺ beam,
100 keV
30 % DC
160 mA total
125 mA after cone

Orange: trigger
Green: current from HVPS
Pink: current on Beam Stop




« crédit P.Stroppa/CEA »

Particles: D⁺ – Extraction Voltage: 100 kV
Pulse Length: 30 ms – Repetition rate: 10 Hz.


I_{BS} (mA)	I_{Tot} (mA)	D ⁺ proportion (%)	U_{IE} (kV)	ϵ (π .mm.mrad)
100	134	75	40	0.14
120	151	80	40	0.19
140	170	82	40	0.39
140	170	82	43	0.32

Examples of emittance measurements
with 140 mA of D⁺ on beam stopper




IFMIF : ION SOURCE AND LEBT INSTALLATION AND START AT ROKKASHO (JAPAN) 2014

- May 2013 : Delivery of ion source and LEBT to Rokkasho
- 24 Oct 2014 : First plasma
- 04 Nov 2014 : First H⁺ Beam extracted
- 05 Nov 2014 : 100keV/105mA 1Hz 50% Duty cycle




H⁺ Beam 10% Duty cycle
V_{HT} : 75 kV
I_{CF} : 40 mA



H⁺ Proportion measurement with Doppler shift analysis

2015 GOAL : commissioning proton and deuteron beams in the first semester



Emittance measurements after 1st solenoid

SPIRAL2: SET UP AND START OF THE DEUTERON ION SOURCE AT SACLAY 2012


- 2009 : First beam with the ion source on BETSI
- 2010-2012 : Installation of the Source inside the vault at Saclay

H⁺ / D⁺ beams

20 / 40 keV

10 mA total


5 mA end LEBT



ION	%
Ions	100%
H ⁺ / D ⁺	81% / 83%
H ₂ ⁺ / D ₂ ⁺	14% / 12,3 %
H ₃ ⁺ / D ₃ ⁺	1,7% / 1,2%
Heavy	3,4% / 3,5%



5mA D⁺ at RFQ injection point



$$\epsilon = 0,231\pi. \text{mm.mrad}$$

Spiral2 deuteron source

LEB2 and LBEC installed at Saclay

SPIRAL2: SET UP AND START OF THE DEUTERON SOURCE AT GANIL (FRANCE)

- 2013 : Installation of the source and all component inside the vault n°3 in Caen
- **19 December 2014 at 18h30** : First H⁺ beam produced for Spiral2



March: installation of the ion source in the Vault n°3 in Spiral2



19 December at 18H30
First H⁺ Beam 3,5mA @20kV

2015 GOAL :
commissioning of H⁺ and D⁺ beam
before RFQ commissioning



- Ions source, RF chain and accelerating column installed on HV platform
- LEBT positioned and aligned


H⁺ beam,
100 keV
100 mA total
70 mA after cone
PULSED ONLY



FAIR LEBT



Accelerating column



Accelerating column and ion source with coils



Source and RF chain on platform

2015 GOAL : Start and commissioning proton beams in the first semester

**R&D PROGRAM IN CEA
FOR ION SOURCE DEVELOPMENT**


Design better ion sources with :

- Higher extracted intensities > 150 mA
- Lower Emittance < $0,2 \pi \text{ mm.mrad}$
- Shorter rise time < 100-200 μs
- Better stability < 1%
- Higher availability > 98%
- Easy maintenance
- Low cost

...

To achieve these improvements we need :

- New models for simulations,
- A polyvalent ion source « at home » that can be used to test new ideas and parameters : ALISES ion source



WARP

« Open source » code

Code 3D –PIC
Time dependant

Physics involved

Dissociation / Ionisation,
Secondary electrons
RF Heating
Plasma thermalization
Bias influence on plasma
Plasma chemistry

First studies in 2012 (PhD S.Nyckees)

This program restarted last October in collaboration with external company Pantechnik (co-financed post doc : R. De Guiran)

Funding for region Ile de France for a computer cluster for massive parallel calculations : ISIPIC



2015 GOAL :

Implement physics process in WARP

Confront simulations and measurements on ALISES ion source

SYNERGIUM

Intensité


Plateforme de recherche sur les accélérateurs à haute intensité

île de France

14/10/2014




ALISES ion source



ALISES : ION SOURCE DETAILS

- Reduction of plasma chamber dimensions
→ For global ion source reduction studies


ALISES
H⁺ beam,
40 keV
40 mA total
PULSED ONLY




- Adaptable RF injection system
→ the optimum injection system

- Extraction gap modification
→ To change particules type

ALISES : PENNING DISCHARGES ANALYSIS



Trapped electrons





Kapton foil

Experimental measurements




Validation of simulation


- R&D financed by SACM internal Funding in 2013
- Macor inserts were placed where electrons are trapped
 - Succeed in higher bias voltage 30kV
 - Extracted current = 18 mA



MACOR inserts inside ALISES source



Extracted current 18mA @30kV



ALISES V2 already designed and built but not yet assembled



Yesterday 2015-01-14

2015 GOAL :

- Finish Assembling and test ALISES v2
- Confrontation of measurements with plasma simulations

We have R&D ideas about all aspects of ion sources :

- Develop plasma simulations and measurements
- Investigate alternative RF sources and injection systems
- Simulate and test different magnetic configurations
- Optimize the geometry of the extraction system
- Think of mechanical and electrical improvements

This R&D requires:

- A local test bench : upgrade of BETSI in progress
- Plasma and beam diagnostics : benefit from our work and experience on other projects (IFMIF, FAIR, ESS...)
- Money, manpower (scientific and **technical**) with dedicated time

**THANK
YOU
FOR
YOUR
ATTENTION**