



Update on J-PARC Project

Nobuhiro KIMURA
Cryogenic Science Center/KEK



Collaborators

KEK

**Y. AJIMA, O. ARAOKA, Y. FUJII, N. HIGASHI,
A. ICHIKAWA, M. IIDA, K. KASAMI, T. KOBAYASHI,
Y. MAKIDA, T. NAKAMOTO, T. OGITSU, H. OHHATA,
T. OKAMURA, K. SASAKI, S. SUGAWARA,
K. TANAKA, A. TERASHIMA, T. TOMARU, and A.
YAMAMOTO**



Contents

- Introduction
- System overview and Design of the Cryogenics
- Status on cryostat components
- Recent status on installation work in the tunnel
- Summary



Contents


- Introduction
- System overview and Design of the Cryogenics
- Status on cryostat components
- Recent status on installation work in the tunnel
- Summary



Introduction

Neutrino physics at J-PARC
Tokai-to-Kamioka (T2K) Long Baseline
 ν Oscillation Experiment

Super-Kamiokande



Kamioka

objective: study the nature of Neutrino in detail

T2K (2009~)

295 km


Tokai

K2K (1999~2005)
250km

KEK J-PARC @JAEA

- Off-axis sub-GeV ν_μ beam from J-PARC 50GeV-PS
- $\sim 3000 \nu_\mu$ CC int./yr (w/o osc.)
- ν_e appearance discovery
- ν_μ disapp. presice meas.
- 5 year construction
- Start experiment in 2009.

Sensitivity on ν_e appearance






Overview of Project History

- 2001FY
 - Design of Neutrino beam line project (T2K) was started with 10 FODO = 40 Superconducting(SC) Magnets
- 2002FY
 - Superconducting Combined Function Magnets system, which consists of 14 doublet: 28 SCFM, was proposed as bending magnet system.
- 2003FY
 - SCFM was approved by internal review in KEK
 - The first production of prototype magnet was started in-house at the KEK
- 2004FY
 - Civil construction work of Neutrino beam line was started at Tokai
 - A prototype magnet was completed and tested in KEK
 - Design of cryostat and cooling system were started
 - Production of the magnets and cryostats were started at Mitsubishi Electric
- 2006FY
 - Continuing magnet production and cryostats
- 2007FY
 - Continuing magnet production and cryostats and started installation work in the tunnel
 - Production of the Transfer line was started
- 2008FY
 - Installation work should be completed and started commissioning on end of 2008.



Contents

- Introduction
- System overview and Design of the Cryogenics
- Status on cryostat components
- Recent status on installation work in the tunnel
- Summary




System Overview

- 28 SCFM*s
 - Dipole 2.6 T
 - Quad 18.6 T/m
 - Length 3.3 m
 - 2 in 1 Cryostat
 - Total Stored Energy: 10MJ (50GeV)
- 13 interconnect cryostats
 - 5 beam monitors
 - 3 correctors
 - 4 quench valves
 - 1 none


*SCFM: Superconducting Combined Function Magnet



Superconducting Combined Function Magnet



Specification



Coil ID.: 173.4mm

Mag. Length: 3300 mm

Mech. Length: 3630 mm @RT

Tmax: < 5.0K
(Supercritical Helium)

Dipole Field: 2.59 T

Quad. Field: 18.6 T/m

Field Error: < 10⁻³

Op. Current: 7345 A

Op. Margin: 72%

Inductance: 14.3 mH

Stored Energy: 386 kJ


of Magnet: 28

SC Cable: NbTi/Cu for LHC

Dipole Outer - L



Structure design of the Cryostat for SCFM




Reduce production cost of the cryostat

- LHC common parts
 - Vacuum vessel (modified)
 - Cold diode for protection
 - Support post
 - Shield bottom tray (modified)
 - Connecting Sleeve
- Two magnets assemble into one cryostat
 - F & D magnets (doublet optics)



Quench Relief Valve

Reference pressure input



Original idea is came from Kautzky type Valve @FNL
 Modified for low temperature use by KEK

Variable Relief Pressure
 with reference pressure
 At Pre-cooling: 1.2 MPa
 In Operation: 0.45 MPa

27	ボルト	SUS316	1	
26	ナット	SUS316	1	
25	スプリング	SUS316L	1	
24	スプリング	SUS316L	1	
23	スプリング	SUS316L	1	
22	スプリング	SUS316L	1	
21	スプリング	SUS316L	1	
20	スプリング	SUS316L	1	
19	スプリング	SUS316L	1	
18	スプリング	SUS316L	1	
17	スプリング	SUS316L	1	
16	スプリング	SUS316L	1	
15	スプリング	SUS316L	1	
14	スプリング	SUS316L	1	
13	スプリング	SUS316L	1	
12	スプリング	SUS316L	1	
11	スプリング	SUS316L	1	
10	スプリング	SUS316L	1	
9	スプリング	SUS316L	1	
8	スプリング	SUS316L	1	
7	スプリング	SUS316L	1	
6	スプリング	SUS316L	1	
5	スプリング	SUS316L	1	
4	スプリング	SUS316L	1	
3	スプリング	SUS316L	1	
2	スプリング	SUS316L	1	
1	スプリング	SUS316L	1	

TOKO VALEX CO., LTD.




Assembling of Inter-connect
 Cryostat
 For Quench Valve



Quench Relief Valve

Conceptual Idea




Reference pressure input

Bellows

Variable Relief Pressure
by reference pressure

Pre-cooling: 1.2 MPa
In Operation: 0.45 MPa

$P > P_{in} = \text{Close}$
 $P < P_{in} = \text{Open}$





Cross section of the Transfer Line

Spacer **GFRP** for Thermal Shield

Spacer **GFRP** for SHe supply and Return Line

SC Bus-bar

- Super Insulation
 - Main Line Polyester
 - Part of connection with Feed Box Polyimide

Design of Heat Loads
 440 W (300K to 60K)
 55 W (60K to 5K)

**A specification of the transfer line for tender was fixed.
 Bidding was started in Feb.
 Contractor will be decided in this April.**

(Nobuhi)



Transfer Line with SC bus-bar

Feed Box (F.B.)


SHe Line (Supply)
 Inner diameter=54.5mm, 100 m, 4.5 K,
 SHe 350 g/s, 0.4 MPa-Abs
With SC-Bus-bar
SHe Line (Return)
 Inner diameter=54.5mm, 100 m, 4.5 K,
 SHe 350 g/s, 0.4 MPa-Abs
Shield Line (Supply)
 Inner diameter=42.6mm, 60 K, 100 m
Shield Line (Return)
 Inner diameter=54.5mm, 80 K, 100 m

Main Arc Tunnel

Sub-tunnel B

Current Leads Box (C.L.)

Sub-cooler (S.C.)






Contents

- Introduction
- System overview and Design of the Cryogenics
- Status on cryostat components
- Recent status on installation work in the tunnel
- Summary




Status on SCFM

- In our project plan, thirty two SCFM products for T2K.
- All of the SCFM are tested using with horizontal cryostat in KEK.
- In this time, twenty eight SCFM have finished performance test without serious troubles.
- These magnets install in the tunnel with cryostats.
- Left four SCFM will be done performance test until mid of 2008.
- These four SCFM will use as reserve magnet.





Cryostat Assembly



transport suport




Status on Dublet Cryostat



Twelve cryostats are completed, and installed in the tunnel.
Left two cryostats and two reserved cryostats are
now under production at Mitsubishi Electric Co..



Status of Transfer Line



Production of Transfer line
was started on end of 2007

First of four units of transfer line
were delivered for KEK.
These units will be installed
in the tunnel on this July.



Contents

- Introduction
- System overview and Design of the Cryogenics
- Status on cryostat components
- Recent status on installation work in the tunnel
- Summary



Status on Doublet Cryostat (1)



On 8th Feb. 2008, installation work of the doublet cryostats were started in the tunnel at Tokai.

The above photograph shows the cryostat into the tunnel by crane.

Left three photographs show the first cryostat in the tunnel.



Status on Doublet Cryostat (2)




Doublet cryostats in the tunnel.
eleven doublet cryostats (11/14) were set on the beam line.
The cryostats were tighten by bolts.



Status on Quench Valve Cryostat



Four Quench Valve inter-connect cryostats were transferred in to the tunnel



Three Quench Valve inter-connect cryostats were set on right position in the system.



Status on other component



Quench pressure relief lines were installed in the tunnel.
The lines will be connected with quench relief valve cryostat
and stack.



Contents

- Introduction
- System overview and Design of the Cryogenics
- Status on cryostat components
- Recent status on installation work in the tunnel
- Summary



Summary

- Twenty eight SCFMs have finished performance test without serious troubles.
- Twelve doublet cryostats have been completed, and installed in the tunnel.
Left two doublet cryostats and two reserved cryostats are now under production at Mitsubishi Electric Co..
- Three quench relief valve cryostats and two corrector magnet cryostats have installed in the tunnel.
- First of four units of transfer line were delivered for KEK.
These units will be installed in the tunnel on this July.
- A cold box manufactured by LINDE and components such as a Helium compressor will be delivered Tokai at mid of May 2008.







J-PARC project and Neutrino beam line

JAEA@Tokai-mura
(60km N.E. of KEK)


	JPARC	NuMI (FNAL)	K2K
E(GeV)	50	120	12
Int.(10^{12} ppp)	330	40	6
Rate(Hz)	0.275	0.53	0.45
Power(MW)	0.75	0.41	0.0052

10^{21} POT(130day) ≒ “1 year”





Incident angle = 0.1, 0.5, 1.0, 1.4 degs.




The beam is distributed uniformly rectangular area. $dX=1\text{cm}, dY=2\text{cm}$

	Beam shield	Beam tube
-		
Material	Copper	Stainless
Radius (mm)	~74	76~84
Thickness(mm)	0, 4, 8, 10	8




Heat input


QuickTime[®] C²
TIFF I LZW J a l i s t E v E c E O a E A
Ç™Ç±ÇÄEsÉNE'EEÇ¼a@ÇEÇzÇ¼Ç...ÇÖIKövÇ-Ç□AB




50GeV 750kW protons with 1.4 degs. hit on beam pipe
without beam shielding




50GeV 750kW protons with 1.4 degs. hit on beam pipe
,Cu shielding,(4mm)



50GeV 750kW protons with 1.4 degs. hit on beam pipe
,Cu shielding,(8mm)








Simple estimation: $\sigma_{th} = \frac{2-\nu}{3(1-\nu)} \cdot E \cdot \int_0^T \alpha \cdot dT$ 100kGy/pulse











$\sigma_{th} = 0.52\text{GPa}$



~ Tensile Strength @ 300K







- 
 -  OFF  1.4
 - 10mm 



- 
 -  π
 -  130mm
 -  10mm


- 
 - 




-
-
-
- ◆
-
-









- - mm OFF
 -
 -
- - 35msec
 - →
 - 1msec
- - 0.1MPa
 - 0.3MPa
 -






– MARS

– 1 w/m, 4000 hr/year






X →
0 Z
50GeV-1W/m












Radiation to Cold Diode

- Influence of Neutron to Cold Diode
 - Intensively studied at CERN by D. Hagedorn
 - ◆ Change Forward Voltage
 - Using LHC Arc Quad Assembly
 - ◆ 7.5kA Operation
 - ◆ Limit; $2 \cdot 10^{14}$ n/cm²






- 
- 
- 
- ◆ 
- ◆ 


- 
- 
- ◆ 
- ◆ 





5. Operation - Warming



Motor Power □ 1.2kW@4.5K □ 2.5kW@80K
 Helium Pump, 300~400 g/s 400kPa





"rC
fXf^fb^N

fTfufgf^flf^D

fTfufgf^flf^B

地下トンネル内 ^A'S^U"rCf%ofCf"

緊急放出ライン

超伝導マグネット

シールド裏り 輻射シールド冷却

トランスファーライン


f r [f e f j ... [f u


fNf%ofCfIfXf^fbfgi^M^o



^A'S^U"rCf%ofCf"




Strict analytical model















- **Quench Protection Heater**
 - Powered by Capacitor Bank



- **Cold Diode**
 - Turn On Voltage: 6V
 - Forward Voltage: 1V



- **Dump Circuit**
 - Protect Cold Diodes and SC Bus Bars
 - Time Constant: 10 sec

- 
- 
- 
- 




Summary of Load (Magnet & Transfer Lines) to Cryogenic System

	4.5 K Level	Remarks	80 K Level	Remarks
Coolant	SHe	4.5 K □ 0.4 MPa	He Gas	60 □ 100 K, 1.2 MPa
Heat Load Estimation	336 W	Including beam loss of 150 W transfer line of 55 W	1419 W	Including transfer line of 440 W
Current Lead	1.0 g/s	8000A	-	
+ 20 % Contingency	403 W + 1.1 g/s		1703 W	
Cold Mass	204 ton	Iron basis	6.8 ton 2.5 ton	Aluminum basis Iron basis
+ 10 % Contingency	225 ton	Iron basis	7.5 ton 2.8 ton	Aluminum basis Iron basis
Inventory	3550 ℓ		1620 ℓ	
+ 10 % Contingency	3900 ℓ		1780 ℓ	
Pressure Drop	84 kPa	300 g/sec, 4.5 K, 0.4 MPaAbs	36 kPa	40 g/sec, 80 K, 1.35 MPa
Design Pressure	>1.4 MPa(G)		>1.4 MPa(G)	




Operation – Pre-cooling






Operation – Magnet Excitation (Steady state)





Operation - Quench






Schedule

	2005	2006	2007	2008
Cryostat w/ 2-SCFMs	1 (proto)	6 (12 Mag.)	6 (12 Mag.)	2 & Install
Transfer Line				Install
Refrig.				Install
PS				Install
Corrector Magnet				Install
Quench Detector				Install



Horizontal Test Bench with the Cryostat



Feed Box

Mass flow rate: 20 ~ 40 g/sec
 Coolant: SHE
 Supply temperature : 4.5 ~ 4.8K
 Supply pressure : 0.35~0.4 MPa Abs

Temperature sensor
 (Lake Shore, Cernox)

Quench protection heater
 as a calibration heater
 $Q_{inpt}=2, 3, 4$ (W)






Summary of Organic Materials in Magnet and Radiation Resistance

1 w/m, 4000 hr/year

- Coil (~30kGy/y)
 - GFRP (10^7 Gy)
 - Polyimide (10^7 Gy)
- Plastic Collar (~10kGy/y)
 - Glass Filled Phenol (10^7 Gy)
- Super Insulator
 - Body (~200Gy/y)
 - ◆ Polyester (10^6 Gy)
 - End (~30kGy/y)
 - ◆ Polyimide ($6 \cdot 10^7$ Gy)
- Support Post (~200Gy/y)
 - GFRP (10^7 Gy)
- Cold Diode
(~200Gy/y, $1.2 \cdot 10^{13}$ n/cm²)
- Elastomer Seals
(~30kGy/y)






New Elastomer Seal for the Cryostat


New EPDM type Elastomer seal were developed with collaboration of KEK, JAEA and Hayakawa Rubber Co..

New Elastomer seal have been tested up to Dose=9.1 MGy with γ ray source.






Hardness and Compression set





Outgas Characteristics of EPDM Elastomer Seal



It is confirmed that new EPDM type elastomer seal can be used up to Dose=1.2 MGy.



Layout of Cryogenic Components

Magnet String & Transfer Line
Inventory: 3900 ℓ,
Cold mass: 225 ton(Fe)


Cold Box & Sub-cooler
SHe Max 300 g/sec at 4.5 K
LHe reserver : 800 ℓ

**3 Recovery Tanks
(for Quench)**
Volume 100 m³×3

Main compressor(MCP)
550 kW
Discharge pressure:1.5 MPaAbs

**Buffer Tank for Main Compressor
(steady state)**
Volume 100m³×1

LN2 > 20000 ℓ
Only precooling and
recooling after quench
18000 ℓ/day
For first heat exchanger
(cold box)



Quench Release Analysis

OKAMURA Takahiro
takahiro.okamura@kek.jp

Contents

- 0. Motivation of this work**
- 1. Conceptual diagram of quench release**
- 2. Analytical model & Method**
- 3. Highlight numerical result**
- 4. Summary**




Conceptual diagram of quench release

Allowable pressure of SC magnet system: 2.0 MPa

**Essential qualification of He gas
Max Pressure of He gas < 2.0 MPa**




**Determination
of Geometric Parameter
I.D. of Relief Valve**





Simulation Model





Governing Equations & Method

Continuity Equation □

$$\frac{\partial}{\partial t}(\rho A) + \frac{\partial}{\partial x}(\rho u A) = 0$$

Momentum Equation □

$$\frac{\partial}{\partial t}(\rho u A) + \frac{\partial}{\partial x}(\rho u u A) = -\frac{\partial}{\partial x}(p A) + G(u)$$

Energy Equation □

$$\frac{\partial}{\partial t}(\rho e A) + \frac{\partial}{\partial x}(\rho e u A) = -p A \frac{\partial u}{\partial x} - \frac{\partial}{\partial x}(q A) + \underbrace{\dot{Q}}$$

Thermal Equation of State □

$$de = \left(\frac{\partial e}{\partial p} \right)_{\rho} dp + \left(\frac{\partial e}{\partial \rho} \right)_{p} d\rho$$

↓
Mass, Momentum, Energy are directly coupled.
(Semi-Implicit Pressure Based Scheme)

Solving Pressure Poisson equation


Finite Difference Method (FDM)+FCT Algorithm

Heat generation term from Magnet.
Most Important Term !!?

↓
1-Dimensional Heat Transfer Model



Heat Transfer Model



Region-1: Energy Balance Equation

$$\rho c_p \frac{\partial T_M}{\partial t} \Delta V = Q \Delta V - q \Delta S, \quad q = \lambda_K \frac{T_M - T_H}{\Delta r_2}$$




Heat Generation term
from Magnet to SHE

$$\dot{Q} = \frac{q \Delta S}{\Delta x}$$




Initial Conditions







Simulation Model






Highlight Result





7. Quench simulation (□D Simulation)



This model is based on an assumption that flow is Two-dimensional
Numerical simulation is carried out involving four magnets, one relief valve, venting line and
buffer tank.



Simulation Method

- **E.Q.: NSE+Equation of State**

$$\frac{\partial \rho}{\partial t} + \nabla \cdot (\rho \mathbf{v}) = 0$$

$$\frac{\partial}{\partial t} (\rho \mathbf{v}) + \nabla \cdot (\rho \mathbf{v} \mathbf{v}) = -\nabla p + \nabla \cdot \boldsymbol{\tau} + \rho \mathbf{g}$$

$$\frac{\partial}{\partial t} (\rho e) + \nabla \cdot (\rho e \mathbf{v}) = -\nabla \cdot \mathbf{q} - p(\nabla \cdot \mathbf{v}) + \boldsymbol{\tau} : \nabla \mathbf{v}$$

$$de = \left(\frac{1}{\varphi \rho} \right) dp - \left(\frac{c^2}{\varphi \rho} - \frac{p}{\rho^2} \right) d\rho$$


where

$$\left\{ \begin{array}{l} \boldsymbol{\tau} = \mu \left\{ \nabla \mathbf{v} + (\nabla \mathbf{v})^T \right\} - \frac{2}{3} \mu (\nabla \cdot \mathbf{v}) \mathbf{I} \\ \mathbf{q} = -\lambda \nabla T \end{array} \right.$$

- **Method: FVM+Pressure Based Scheme**
- **Coordinate: BFC**



7. Simulation Results at 4/4 Magnets Quench





Bas line



Magnet(Heat Input)

Pressure Profile



Quench relief valve



Temperature Profile



Density Profile




(NOUUNHO KIMUKA 1 HE ZHU ZHICHAO-KEL cooperation program workshop - 28/MARCH/2008)



Required Cooling Capacity



SHe Flow Rate	max 300 g/s
SHe Condition	0.4 MPa(A), 4.5 K
SHe Return	4.9 K
Thermal Load to SHe Flow	410 W
Pressure Head of SHe	85 kPa
Current Lead cooling gas	1.1 g/s (1 pair)
Shield Temperature	60 □ 100 K
Shield Cooling	Cold Helium Gas
Thermal Load to Shield Line	1710 W
Shield Cooling Gas Condition	Not specified
LN2 usage	Only Pre-cooling and re-cooling after quench
Pre-cooling duration	< 20 days
Re-cooling duration	<6 hours (30GeV operation)



Schematic diagram of SHe circulation system



Required Cooling Capacity - Estimation



$$PressureHead = f \frac{L}{D_h} \frac{\rho u^2}{2}$$

f : Friction Coefficient, L : Length,
 D_h : Hydraulic Diameter, u : Flow Velocity

Expected Operational Flow Rate :
 300 g/s □ Pump Load : < 300 W
 Mag. Temp. : ~ 4.8 K

$$TotalLoad =$$

[Mag & Trans.T + 20%]
 + [PumpLoad]
 + [Sub-coolerLoad : 143W]

$$PumpLoad = \frac{\Delta P \dot{M}}{\rho \eta}$$

Mass-flow rate is controlled to be 300 g/s at the maximum.




Required Refrigeration Capacity – Design by Contractor

		Thermal Load @4.5 K Level	Thermal Load @shield Level
KEK Requirement	Magnet & Transfer Line	410 W + 1.1 g/s	1710 W
	SHe Flow conditions	Max 300 g/s, 4.5 K, 0.4 MPa Pressure Head 85 kPa	
Contractor Design	SHe Pump Load	330 W	
	Sub-cooler, Transfer Line b/w CB	150 W	250 W
	Required Refrigeration	890 W + 1.1 g/s → 1.0 kW	1960 W → 2 kW
	+ 20 % Margin	1.2 kW	2.4 kW

Taiyo-Nissan Co. in the business collaboration with LINDE won the bid.



Conceptual Flow Diagram





Summary

- **A new Implicit Continuous-fluid Eulerian code for SHe venting simulation has been developed by means of 1 & 2 Dimensional Heat transfer model.**
- **Maximum Pressure is about 1.8 MPa and lower than allowable pressure of the magnet under the present relief valve and emergent exhaustion line design conditions.**



Heat Load of the Cryostat

