

# LHC Overview & Status





# Content

1. Accelerator complex
2. Energy Stored in the Magnets
  - Quench Protection System
  - Power Interlock System
  - Energy Extraction
3. Energy Stored in the Beams
  - Beam Dump System
  - Collimation System
4. Machine Protection System
5. Overall Strategy for Commissioning:
  - HW Commissioning
  - Machine Checkout
  - Beam Commissioning
    - Stage A
    - Stage B
    - Stage C&D
6. Documentation & Human Resources
7. Conclusions



# Accelerator complex for p




**The  
15-m long  
LHC cryodipole**

**8.7 T**  
**11.8 kA / 7 MJ**  
**1.9 K**  
**1232 cryodip.**


	<u>Top energy(GeV)</u>	<u>Circumference(m)</u>
LINAC2	0.12	30
PSB	1.4	157
CPS	26	628 = 4 PSB
SPS	450	6911 = 11 x PS
<b>LHC</b>	<b>7000</b>	<b>26657 = 27/7xSPS</b>



# QRL (Cryogenic Line Installation)



He inventory per sector



+ 1260 T LN2 per sector




# LHC Dipoles Installation







# Interconnection






# Inner Triplet



\* Protect Inner Triplet (TAS) and D2 (TAN) from particles coming from the IP



# LHC Arc



LHC TDR



- MBB: Main Dipole
- MQ: Main Quadrupole
- MQT: Trim Quadrupole
- MQS: Skew Trim Quadrupole
- MO: Lattice Octupole
- MSCB: Sextupole (Skew Sextupole)+Orbit Corrector
- MCS: Spool Piece Sextupole
- MCDO: Spool Piece Octupole + Decapole
- (BPM: Beam Position Monitor)

~ 9000 magnets powered with ~1700 power converters



# Contents

1. Accelerator complex
2. Energy Stored in the Magnets
  - Quench Protection System
  - Energy Extraction
  - Power Interlock System
3. Energy Stored in the Beams
  - Beam Dump System
  - Collimation System
4. Machine Protection System
5. Overall Strategy for Commissioning:
  - HW Commissioning
  - Machine Checkout
  - Beam Commissioning
    - Stage A
    - Stage B
    - Stage C&D
6. Documentation & Human Resources
7. Conclusions



# Energy Stored in the Magnets

**~ 10 Gjoule corresponds to ...**

... an aircraft carrier at battle-speed of  
55 km/h



the energy of ~3 Tons TNT  
the energy of 370 kg dark chocolate

More important than the amount of energy is ...  
**How fast (an safe) can this energy be  
released?**



# Energy Stored in the Magnets

If not fast and safe ...



During magnet test campaign, the **7 MJ** stored in one magnet were released into one spot of the coil (inter-turn short)



# Energy Stored in the Magnets: Quench & Quench Protection System

- **A Quench is the phase transition of a superconducting to a normal conducting state**
- **Quenches are initiated by an energy release of the order of mJ:**
  - **Movement of the superconductor by several  $\mu\text{m}$  (friction and heat dissipation)**
  - **Beam losses:**
    - **@7 TeV 0.6 J/cm<sup>3</sup> can quench a dipole; this energy density can be generated by  $10^7$  protons**
    - **@450 GeV (injection energy),  $\sim 10^9$  protons are needed**
  - **Failure in cooling**



# Energy Stored in the Magnets: Quench & Quench Protection System

## Quench Protection System


- To limit the temperature increase after a quench
  - The quench has to be detected → **Quench Detectors\***
  - The energy is distributed in the magnet by force-quenching the coils using **Quench Heaters\***
  - The stored energy is released in a controlled way → **Cold by-pass diodes\*** & **Energy Extraction System**
  - The magnet current is switched off within  $\ll 1$  second → **Power Interlock System**
- Failure in QPS:
  - False quench detection: down time of some hours 😞
  - Missed quench: damage of magnet, down time 30 days ⚠️

\* On every SC magnet



# Energy Stored in the Magnets: Quench & Quench Protection System


LHC Main Dipole System in one sector





# Magnet Energy: Energy Extraction System

- During normal operation every ramp down of the magnets implies energy extraction, but this takes  $\sim 20$  min  $\rightarrow$  too slow in case of a quench
- A dedicated Energy Extraction System for quench protection is needed
- There are 32 EES for the 24 13kA main circuits (dipoles & quadrupoles) (+ the EES for the 600 A correctors)
- This system releases the energy in 104 s for the dipoles ( $-125$  A/s) and in 40 s for the quadrupoles ( $-325$  A/s)




13kA Energy Extraction Facilities in the UA's  
for LHC Main Dipole and QF/QD circuits



# Magnet Energy: Power Interlock Controller

- **36 PICs in LHC for the SC magnets (warm magnets also have PICs)**
- **1 PIC per Powering Subsector**

Power Converters  
QPS  
Cryo  
UPS, AUG






# Contents

1. Accelerator complex
2. Energy Stored in the Magnets
  - Quench Protection System
  - Power Interlock System
  - Energy Extraction
3. Energy Stored in the Beams
  - Beam Dump System
  - Collimation System
4. Machine Protection System
5. Overall Strategy for Commissioning:
  - HW Commissioning
  - Machine Checkout
  - Beam Commissioning
    - Stage A
    - Stage B
    - Stage C&D
6. Documentation & Human Resources
7. Conclusions



# Energy Stored in the Beams



$$E_{p^+} = 7 \text{ TeV}$$

$$K_b = 2808$$

$$\text{Num } p^+/\text{bunch} = 1.15 \times 10^{11}$$


$$E_{\text{beam}} = 362 \text{ MJules}$$

Nominal values

Enough to melt 500 kg of copper




# Energy Stored in the Beams






# Energy Stored in the Beams: Beam Dump System


**Configuration du système d'arrêt de faisceau au Point 6**



Beam Dump Block  
(graphite)  
~ 8 m




Is the only system in LHC able to  
absorb the full nominal beam






# Energy Stored in the Beams: Collimation System



Collimation System Functionality:

1. Absorb beam halo to avoid quenches
2. Once beam losses appear they protect the equipment and experiments. If BLMCs > Threshold → Beam Interlock → Beam Dump



E.g. Settings of collimators @7 TeV with luminosity optics

Very tight settings → orbit feedback!!






# Contents

1. Accelerator complex
2. Energy Stored in the Magnets
  - Quench Protection System
  - Power Interlock System
  - Energy Extraction
3. Energy Stored in the Beams
  - Beam Dump System
  - Collimation System
4. Machine Protection System
5. Overall Strategy for Commissioning:
  - HW Commissioning
  - Machine Checkout
  - Beam Commissioning
    - Stage A
    - Stage B
    - Stage C&D
6. Documentation & Human Resources
7. Conclusions




# Machine Protection System





# Machine Protection System: Beam Interlock



153 User Systems distributed over 27 km




# Contents

1. Accelerator complex
2. Energy Stored in the Magnets
  - Quench Protection System
  - Power Interlock System
  - Energy Extraction
3. Energy Stored in the Beams
  - Beam Dump System
  - Collimation System
4. Machine Protection System
5. Overall Strategy for Commissioning:
  - HW Commissioning
  - Machine Checkout
  - Beam Commissioning
    - Stage A
    - Stage B
    - Stage C&D
6. Documentation & Human Resources
7. Conclusions



# Overall Strategy for Commissioning



## Hardware Commissioning

Thorough commission of technical systems:

- Magnets, vacuum, cryo, PC, quench detection, energy extraction, RF, beam instrumentation, kickers, septa, collimators, absorbers, etc.
- Services: AC distribution, water-cooling, ventilation, access control, safety, etc.

### Stages:


1. Individual system test
2. Global system test

### Commissioned energy:

1. 2008 →  $E_b = 5.5$  TeV (no training quenches)
2. 2009 →  $E_b = 7$  TeV ?? (magnet training required)



# Overall Strategy for Commissioning



## Machine Checkout


- Drive all systems through the standard operational sequence (synchronized)
- Check Control System functionality from **CCC high-level software applications**
- Check beam instrumentation acquisition chain
- Check timing synchronization
- Check all equipment control functionality
- Check machine protection and interlock system

### Stages:

1. Individual system test. First integration into the OP group
2. Multi-system test, e.g. Machine Protection (BLM, BIS, LBDS)
3. Dry run: drive the whole machine through the nominal sequence.



# Overall Strategy for Commissioning



## Stage A: Pilot physics run

- First collisions
- 43 bunches, no crossing angle, no squeeze, moderate intensities
- Push performance
- Performance limit  $10^{32} \text{ cm}^{-2}\text{s}^{-1}$  (event pileup)

## Stage B: 75ns operation

- Establish multi-bunch operation, moderate intensities
- Relaxed machine parameters (squeeze and crossing angle)
- Push squeeze and crossing angle
- Performance limit  $10^{33} \text{ cm}^{-2}\text{s}^{-1}$  (evt pileup)

## Stage C: 25ns operation I

- Nominal crossing angle
- Push squeeze
- Increase intensity to 50% nominal
- Performance limit  $2 \cdot 10^{33} \text{ cm}^{-2}\text{s}^{-1}$

## Stage D: 25ns operation II

- Push towards nominal performance
- Requires hardware updates: collimators and beam dump system
- Performance goal:  $10^{34} \text{ cm}^{-2}\text{s}^{-1}$




# Beam Commissioning with $p^+$

- LHC Design Parameters:

Design Parameters	
Lumi IP 1,5 ( $\text{cm}^{-2} \text{s}^{-1}$ )	$10^{34}$
Lumi IP 2,8 ( $\text{cm}^{-2} \text{s}^{-1}$ )	$5 \cdot 10^{32}$
$\sigma_{xy}$ IP 1,5 ( $\mu\text{m}$ )	16.7
$\sigma_{xy}$ IP 2,8 ( $\mu\text{m}$ )	70.9
Crossing angle ( $\mu\text{rad}$ )	285

Nominal Settings	
$E_{\text{beam}}$ (TeV)	7
# $p^+$ /bunch	$1.15 \cdot 10^{11}$
# bunches/beam	2808
$E_{\text{beam}}$ Stored (MJ)	362
$\epsilon_n^{xy}$ ( $\mu\text{m rad}$ )	3.75
Bunch length (cm)	7.5
$\beta^*$ (IP: 1,2,5,8) (m)	0.55, 0.55, 10, 10





# Beam Commissioning with $p^+$ Stage A

- Start as simple as possible
- Change 1 parameter ( $k_b$ ,  $N$ ,  $\beta^*$ ) at a time
- All values for:
  - ▣ nominal emittance
  - ▣ 7 TeV
  - ▣ 2 m  $\beta^*$  (IP: 1&5)

$$L = \frac{N^2 k_b f \gamma}{4\pi \epsilon_n \beta^*} F$$

$$EvtRate / Cross = \frac{L \sigma_{TOT}}{k_b f}$$

**Protons/beam  $\leq 10^{13}$   
(LEP beam currents)**


**Stored energy/beam  $\leq 10$  MJ  
(SPS fixed target beam)**

Parameters			Beam levels		Rates in 1 and 5		Rates in 2	
$k_b$	$N$	$\beta^*$ 1,5 (m)	$I_{beam}$ proton	$E_{beam}$ (MJ)	Luminosity ( $cm^{-2}s^{-1}$ )	Events/crossing	Luminosity ( $cm^{-2}s^{-1}$ )	Events/crossing
1	$10^{10}$	11	$1 \cdot 10^{10}$	$10^{-2}$	$1.6 \cdot 10^{27}$	$\ll 1$	$1.8 \cdot 10^{27}$	$\ll 1$
43	$10^{10}$	11	$4.3 \cdot 10^{11}$	0.5	$7.0 \cdot 10^{28}$	$\ll 1$	$7.7 \cdot 10^{28}$	$\ll 1$
43	$4 \cdot 10^{10}$	11	$1.7 \cdot 10^{12}$	2	$1.1 \cdot 10^{30}$	$\ll 1$	$1.2 \cdot 10^{30}$	0.15
43	$4 \cdot 10^{10}$	2	$1.7 \cdot 10^{12}$	2	$6.1 \cdot 10^{30}$	0.76	$1.2 \cdot 10^{30}$	0.15
156	$4 \cdot 10^{10}$	2	$6.2 \cdot 10^{12}$	7	$2.2 \cdot 10^{31}$	0.76	$4.4 \cdot 10^{30}$	0.15
156	$9 \cdot 10^{10}$	2	$1.4 \cdot 10^{13}$	16	$1.1 \cdot 10^{32}$	3.9	$2.2 \cdot 10^{31}$	0.77



# Beam Commissioning with p+

## Stage A







# Beam Commissioning in the Transfer Lines




## Transfer line commissioning



Courtesy of J. Uythoven




# Injection Test 1






# Injection Test 1

- Achieved
  - Synchronization SPS – LHC
  - **Beam 1** injected IP2
  - Through to collimators in IP3 first shot
  - Trajectory correction
  - Kick-response measurements
  - Off-energy measurements (dispersion)
  - Explored the aperture
  - Quench
- Discovered
  - Aperture restriction in the injection line
    - Traced to misaligned vacuum pump
  - Optics problem IP3
    - Polarity convention QTL







# Injection Test 2






# Injection Test 2

- Achieved
  - **Beam 2** injected IP8
  - Through to collimators in IP7 first shot
  - Trajectory correction
  - Kick-response measurements
  - Off-energy measurements (dispersion)
  - Explored the aperture
  - **Beam 1** injected IP2
  - Through to collimators in IP3
  - Aperture in injection region OK
  - Polarity correction confirmed
  - Interleaved injection
- Discovered
  - Optics problem at the end of the TI8 line






# Injection Test 3






# Injection Test 3

- Achieved
  - **Beam 2** injected IP8
  - Threaded to dump in IP6
  - Steered then inject and dump
  - **Beam 1** injected IP2
  - Threaded through to coll in IP5
- Discovered
  - Optics problem in IP7
    - Polarity convention on Q6
  - Optics problem in IP4
    - Polarity convention





# 10<sup>th</sup> of September






# 10<sup>th</sup> of September

- Achieved
  - Beam 1 injected IP2
  - Threaded around the machine in 1h
  - Trajectory steering gave 2 or 3 turns
  
  - Beam 2 injected IP8
  - Threaded around the machine in 1h30
  - Trajectory steering gave 2 or 3 turns
  - Q and Q' trims gave a few hundred turns




# Beam 1 – First turn trajectory








# Beam 2 – First turn trajectory






# Beam 2 – first turn dispersion measurement

horizontal dispersion beam 2, 1st turn






# Beam 2: Longitudinal Bunch Profile






# Beam 2 closed orbit






# Beam 2 beta measurement





# Beam 2 integer tunes





# Beam 2 tunes

Tune Viewer - LHC - On-demand FFT system B2

File Run Configure Help

RBAC User: LHC LHC.BQBBQ.UA47.FFT2\_B2 LHC.BQPLL.UA43.PLL\_B2 LHC.OFSU

Info FFT PLL Data Sets Feedback

**Q-FPGA** Tune Measurements CERN

LHC - B2 - Fill#830  
2008-09-10 21:38:52  
RAW&FFT: 256 turns@1.0Hz  
no excitation

Q1 = .3092	Qx = .3089
Q2 = .2333	Qy = .2337
C-  = .0106	
Q'x = ???	
Q'y = ???	

Comments:  
no comment

Spawn TuneViewer Display

Graph Mag H ACQ# 0 Scale

LHC - B2 - fill #830 - no comment - LHC.BQBBQ.UA47.FFT2\_B2 - 2008-09-10 2...

horizontal amplitude [dB]

frequency [frev]

Graph RAW V ACQ# 0 Scale

LHC - B2 - fill #830 - no comment - LHC.BQBBQ.UA47.FFT2\_B2 - 2008-09-10 2...

vertical amplitude [a.u.]

turn

21:38:57 - <4> Start multiple monitoring on user LHC



# Beam 2 fast BCT (Beam Current Transformer)

LHC Fast BCT V0.1-2007

Views [Icons] More [Icons]

Contour Ring 2 [10/09/08 21:39:36]

turn

bunch

Bunch intensities [10/09/08 21:39:36]

turn: 1

intensity

bunch

Single bunch intensity [10/09/08 21:39:36]

bunch: 3506

intensity

turn

Acquisition Configuration

Capture Settings

B 1  B 2

Bunch selection

Continuous  Individual

3500-3510

Turns: 144

Turn Increment: 2

Trigger Condition

GMT

RF Injection Prepulse

Software

Get Set


Console Running tasks

```
captureSettingTime (String:1) --> Wed Sep 10 21:29:21 2008
21:39:36 - Ready.
```

21:26:07 - selected ring: 2




# Beam dilution sweep on dump block






# Beam 2 captured – mountain range display





# Beam 2 wire scanner





# Fast start 10, 11 and 12

- All done in 3 days
- Made possible by
  - Meticulous preparation
    - Magnetic model data
    - Sophisticated settings generation
    - Dry runs
    - Injection tests
  - Powerful control system (LSA)
  - Powerful instrumentation working very quickly
  - Logging a multitude of parameters
- Allowed
  - early look at several machine parameters
  - systematic check of orbit system





# Beam Commissioning with p+

## Stage B: Intermediate physics run

- Relaxed crossing angle (250  $\mu$ rad)
- Start un-squeezed
- Then go to where we were in stage A
- All values for
  - nominal emittance
  - 7 TeV
  - 10 m  $\beta^*$  in points 2 and 8

$$F = 1 / \sqrt{1 + \left(\frac{\theta_c \sigma_z}{2\sigma^*}\right)^2}$$

Protons/beam  $\approx$  few  $10^{13}$

Stored energy/beam  $\leq$  100 MJ

Parameters			Beam levels		Rates in 1 and 5		Rates in 2 and 8	
$k_b$	N	$\beta^*$ 1,5 (m)	$I_{\text{beam}}$ proton	$E_{\text{beam}}$ (MJ)	Luminosity ( $\text{cm}^{-2}\text{s}^{-1}$ )	Events/crossing	Luminosity ( $\text{cm}^{-2}\text{s}^{-1}$ )	Events/crossing
936	$4 \cdot 10^{10}$	11	$3.7 \cdot 10^{13}$	42	$2.4 \cdot 10^{31}$	$\ll 1$	$2.6 \cdot 10^{31}$	0.15
936	$4 \cdot 10^{10}$	2	$3.7 \cdot 10^{13}$	42	$1.3 \cdot 10^{32}$	0.73	$2.6 \cdot 10^{31}$	0.15
936	$6 \cdot 10^{10}$	2	$5.6 \cdot 10^{13}$	63	$2.9 \cdot 10^{32}$	1.6	$6.0 \cdot 10^{31}$	0.34
936	$9 \cdot 10^{10}$	1	$8.4 \cdot 10^{13}$	94	$1.2 \cdot 10^{33}$	7	$1.3 \cdot 10^{32}$	0.76



# Beam Commissioning with p+ Stage C&D: 25 ns Operation

- Nominal crossing angle (285  $\mu$ rad)
- Start un-squeezed
- Then go to where we were in stage B
- All values for
  - nominal emittance
  - 7 TeV
  - 10m  $\beta^*$  in points 2 and 8

Protons/beam  $\approx 10^{14}$

Stored energy/beam  $\geq 100$  MJ

Parameters			Beam levels		Rates in 1 and 5		Rates in 2 and 8	
$k_b$	N	$\beta^*$ 1,5 (m)	$I_{\text{beam proton}}$	$E_{\text{beam}}$ (MJ)	Luminosity ( $\text{cm}^{-2}\text{s}^{-1}$ )	Events/crossing	Luminosity ( $\text{cm}^{-2}\text{s}^{-1}$ )	Events/crossing
2808	$4 \cdot 10^{10}$	11	$1.1 \cdot 10^{14}$	126	$7.2 \cdot 10^{31}$	$\ll 1$	$7.9 \cdot 10^{31}$	0.15
2808	$4 \cdot 10^{10}$	2	$1.1 \cdot 10^{14}$	126	$3.8 \cdot 10^{32}$	0.72	$7.9 \cdot 10^{31}$	0.15
2808	$5 \cdot 10^{10}$	2	$1.4 \cdot 10^{14}$	157	$5.9 \cdot 10^{32}$	1.1	$1.2 \cdot 10^{32}$	0.24
2808	$5 \cdot 10^{10}$	1	$1.4 \cdot 10^{14}$	157	$1.1 \cdot 10^{33}$	2.1	$1.2 \cdot 10^{32}$	0.24
2808	$5 \cdot 10^{10}$	0.55	$1.4 \cdot 10^{14}$	157	$1.9 \cdot 10^{33}$	3.6	$1.2 \cdot 10^{32}$	0.24
Nominal			$3.2 \cdot 10^{14}$	362	$10^{34}$	19	$6.5 \cdot 10^{32}$	1.2



# Contents

1. Accelerator complex
2. Energy Stored in the Magnets
  - Quench Protection System
  - Power Interlock System
  - Energy Extraction
3. Energy Stored in the Beams
  - Beam Dump System
  - Collimation System
4. Machine Protection System
5. Overall Strategy for Commissioning:
  - HW Commissioning
  - Machine Checkout
  - Beam Commissioning
    - Stage A
    - Stage B
    - Stage C&D
6. Documentation & Human Resources
7. Conclusions



# Documentation

- Hardware Commissioning Coordination

- <http://hcc.web.cern.ch/hcc/>

- Machine Checkout

- <http://wikis/display/LHCOP/LHC+Machine+Checkout>

- LHC Commissioning Procedures

- [http://lhccwg.web.cern.ch/lhccwg/overview\\_index.htm](http://lhccwg.web.cern.ch/lhccwg/overview_index.htm)

CERN  
CH-1211 Geneva 23  
Switzerland



LHC Project Document No.

LHC-OP-BCP-0002 rev 0.2

CERN Div./Group or Supplier/Contractor Document No.

LHCCWG

EDMS Document No.

850423

Date: 2007-08-03

## Beam Commissioning Procedure

### LHC COMMISSIONING WITH BEAM: PHASE A.1 (FIRST TURN)

#### Abstract

This document describes the LHC beam commissioning procedures for the first turn. It covers the entry conditions, the commissioning procedures and exit conditions of this phase. Possible problems and open questions are also listed.

*Prepared by :*  
R.Alemany Fernandez  
B.Goddard  
M.Gruwé  
V.Kain  
L.Ponce  
S.Redaeli  
W.Venturini

*Checked by :*  
LHCCWG

*Approved by:*  
R.Bailey  
O.Bruning  
P.Collier  
M.Lamont  
S.Myers

On behalf of the  
LHCCWG

#### LHCCWG list:

R.Alemany Fernandez, G. Arduini, R. Assmann, R.Bailey, O.Bruning, H.Burkhardt, A.Butterworth, P.Collier, S.Fartoukh, M.Giovannozzi, B.Goddard, J.-J.Gras, M.Gruwé, R.Jones, V.Kain, P.Koutchouk, M.Lamont, A.MacPherson, L.Ponce, S.Redaeli, R.Saban, F.Schmidt, R.Schmidt, R.Steinhausen, E.Todesco, J.Uythoven, W.Venturini Delsolaro, J.Wenninger, T.Wijnands, F.Zimmermann

#### Approval list:

M.Barnes, F.Bordry, L.Bottura, L.Bruno, T.Camporesi, E.Carlier, P.Ciriani, L.Ducimetiere, K.Eggert, L.Evans, M.Ferro-Luzzi, R.Garoby, M.Gyr, J.-M.Jimenez, Y.Kadi, A.Koschik, J.-T.Kramer, J.Letty, P.Lebrun, T.Linnecar, D.Macina, S.Maury, V.Mertens, K.-H.Mess, G.Mornacchi, M.Nessi, Y.Papaphilippou, W.Rieger, G.Roy, H.Schmickler, A.Schopper, F.Strubin, G.Tranquille, E.Tsesmelis, R.VanWeelderden



# Human Resources

## Beam Commissioning



Machine Coordinators



Engineers In Charge (EIC)



Operators



Commissioners In Charge (CIC)



HWC Team



# Summary

- The LHC commissioning is divided in three steps:
  - Hardware Commissioning
  - Machine Checkout
  - Beam Commissioning
- To tackle the machine unprecedented complexity and potential danger (energy stored in the magnets and in the beam), each step is divided in well defined phases
- The success of the commissioning relies, among other things, upon:
  - Carefull elaboration of procedures (Documentation)



# Acknowledges

The content of this presentation has been elaborated from material coming from the

LHC Commissioning Working Group

and

Hardware Commissioning Coordination Group




# Incident of September 19<sup>th</sup> 2008

- During a few days period without beam
- Making the last step of dipole circuit in sector 34, to 9.3kA
- At 8.7kA, development of resistive zone in the dipole bus bar splice between Q24 R3 and the neighboring dipole
- Electrical arc developed which punctured the helium enclosure
- Helium released into the insulating vacuum
- Rapid pressure rise inside the LHC magnets
  - Large pressure wave travelled along the accelerator both ways
  - Self actuating relief valves opened but could not handle all
  - Large forces exerted on the vacuum barriers located every 2 cells
  - These forces displaced several quadrupoles and dipoles
  - Connections to the cryogenic line affected in some places
  - Beam vacuum also affected




# LHC cryodipole (1232 of them)





# All have to be interconnected (quads too)





# Interconnections


Interconnections the superconducting magnets of LHC means:

- 1695 magnet-to-magnet interconnects
- 224 magnet to QRL interconnects

Each magnet to magnet interconnect consists of:


- ✓ 18 assembly actions divided in 9 interventions
- ✓ 5 leak tightness check
- ✓ 5 electrical tests
- ✓ 1 RF test

**For each sector this is:**  
**1964 assembly interventions**  
**226 electrical tests on sub-assemblies**  
**70 vacuum tests on sub-assemblies**  
**14 RF test on sub-assemblies**






# Bus bar interconnection





# Hypothesis



Bus Bar's  
Insulation


Heat exchange with  
He II

- Temperature increase due to an excessive resistance
- Superconductor quenches and becomes resistive at high current (temperature increase due to the resistance).
- Up to a certain current, the Copper can take it (cooled by the He II).
- Beyond a certain current, 'run-away' of the temperature, splice opens, electrical arc ...






# Consequences



- Considerable collateral damage over few hundred metres
- Contamination by soot of beam pipes
- Damage to superinsulation blankets
- Large release of helium into the tunnel (6 of 15 tonnes)

**Insulating vacuum barrier every 2 cells in the arc → Some moved**





# Repair


- Present strategy assumes treating all magnets Q19 to Q31
- May have to treat slightly further outside this zone (to Q33)
- Nearly all the components are at CERN
- Critical components are beam screens and SSS bottom trays
- Estimate for magnets (preliminary) November 08 to March 09
- Then have to finish interconnection, cool down, power test



# Outside sector 34


- All data from hardware commissioning carefully scrutinized
- Anomalous cryogenic behaviour found in sector 12 at 7kA
  - Higher than nominal heat load in cryogenic sector 15 R1
- Controlled tests made late October at different currents
- Calorimetric measurements
  - Measure temperature increase and
  - Derive rate of energy deposition
  - Fit Energy deposition vs current
  - Deduce equivalent resistance

Nominal  
dissipation





# Calorimetric results so far (November)





# Electrical results so far (November)

- Electrical measurements
  - Dedicated electronics needed for inter-magnet splices
  - QPS system used for internal magnet splices
  - S12 15R1
    - All inter-magnet splices measured to be similar, around  $0.3\text{n}\Omega$
    - Magnet B16.R1 measured to have  $100\text{n}\Omega$  !!!
  - S12 19R1
    - Nothing found; traced to a feature of cryogenic system
  - S12 31R1
    - Nothing found; calorimetric fit in any case is very poor
  - S67 31R6
    - Magnet B32.R6 measured to have  $45\text{n}\Omega$  !!!
  - S78
    - Nothing found



# Other measures

- From the analysis of the incident, the following modifications and consolidations are under consideration:
    - Upgrade of the quench protection system for protection against symmetric quenches (was already in the pipeline before Sector 34 incident)
    - Upgrade of the quench protection system for precision measurements and protection of all interconnects
    - Modifications of commissioning procedure to include calorimetric information and systematic electrical measurements
    - Addition of pressure release valves on EVERY dipole cryostat
      - note that this probably requires warming up
- Strategy for implementing this is not yet finalised



# Timescales for restart will be determined by

- Efficiency of logistics of magnets removal / installation
- Efficiency of magnet repair
- Efficiency of beam pipe repair / cleaning
- Efficiency of interconnection activities
- Strategy adopted to ensure no repeat is possible
- Time to cool down
- Time to re-commission power circuits